

Bongaigaon Medical College

QA No. CGM(D&S)/APDCL/LAR/Bongaigaon Medical College /2025-26/38 Dt. 13.05.2026

			Grand Total	
Sl. No.	Item Description	Unit		
1	GI Steel Tubular pole , SP-66	No.	4	BSS
2	GI Steel Tubular pole , SP-76	No.	663	✓
3	GI Steel Tubular pole , SP-80	No.	24	✓
4	33 KV Isolator without E/S., 800 Amps	Set	6	
5	33 KV VCB 1250 A with M Structure	No.	1	
6	33 KV C&R Panel for Feeder	No.	1	
7	33 KV CT ,400-200/5-5-5 A	Set	1	
8	33 KV LA, Line type (6+2)	Set	9	
9	33 KV LA, Station type (6+2)	Set	4	
10	33 KV Pin Insulator, Poly	No.	1802	GFP for wardo Jaisco
11	33 KV Poly. Disc Insulator, 90 KN , T&C	No.	18	✓
12	H/F. for Disc , Tension type	No.	18	✓
13	G I Nuts & Bolts	Kg	1930	✓ R.H.
14	G I pole clamp, 50x6 mm (2550+926), (515+65)	No.	4129	R.H.
15	G I Channel 100x50x6x3200 mm	No.	536	✓
16	G I Channel 100x50x6mm	Mtr.	48	✓
17	GI Angle 50x50x6 mm for Bracing	Mtr.	3200	✓
18	GI Angle 50x50x6 mm for Guarding	Mtr.	2066	✓
19	GI Angle 50x50x6x1000 mm for Tie	No.	1362	✓
20	GI Angle 50x50x6 mm for Jam	Mtr.	128	✓
21	GI Strip 25x3 mm	Mtr.	10	✓
22	GI Strip 60x5 mm	Mtr.	10	✓
23	33 KV V cross arm	No.	465	✓
24	33 KV Top Cleat 100x50x6x350mm	No.	465	✓
25	33 KV AAAC Covered conductor 1x241sq. Mm	Mtr.	58820	
26	Mid span Jointing Kit for 241sq. Mm MVCC	No.	125	
27	Cable termination Kit for 241sq. Mm MVCC	No.	687	
28	33 KV Tension Insulator for 241sq. Mm MVCC	No.	717	
29	33KV Tension H/F for 241sq. Mm MVCC	No.	717	
30	Cable tie for 241sq. Mm MVCC	No.	1775	
31	33 KV Danger Plate	No.	677	✓
32	HT Stay set	Set	170	✓
33	HT Guy Insulator	No.	170	
34	GI Stay wire , 7/10 swg	Kg	1436	
35	GI Wire, 8 SWG	Kg	19075	
36	Barbed Wire	Kg	1292	
37	G I Earth Pipe 50 mm dia , 3 mtr.	No.	733	✓
38	11 KV Pin Insulator , Poly	No.	1387	✓ Jaisco
39	ACSR Wolf	Km	0.3	✓
40	ACSR Raccoon	Km	41.523	✓
41	ACSR Rabbit	Km	251.9	
42	11 KV Disc insulator , 70 KN,T&C	No.	492	✓

43	H/F for Disc for Raccoon	No.	492	GRP. R.H.
44	Tension clamp for Raccoon	No.	492	
45	Tension clamp for Wolf	No.	18	
46	PG Clamp for Raccoon	No.	30	✓
47	PG Clamp for raccoon	No.	486	✓
48	G I Channel 100x50x6x2200 mm	No.	390	✓
49	33 KV XLPE Cable 1x630 sq. mm	Mtr.	2525	
50	Cable Kit for above	No.	40	
51	HDPE Pipe , 110 mm dia , PE 100(210+56)	Mtr.	336	
52	CI Spun pipe 300 mm dia 5.5 m length (60+6)	No.	89	
53	Bend for CI Spun pipe (60+6)	No.	88	
54	33 KV D O Fuse , 150 amps	Set	1	
55	33 KV Gang switch, 800 Amps	Set	9	
56	LT Angle cross arm 40x40x6x500 mm	No.	991	✓
57	LT Pin Insulator	No.	2092	
58	LT GI Pin	No.	2092	
59	LT Shackle insulator	No.	556	
60	LT Shackle Strep	Set	556	
61	11 KV XLPE cable 1x630 sq. mm	Mtr.	200	
62	Cable Kit for above ,Out door	No.	8	
63	11 KV LA , Station type	Set	2	
64	11 KV Gang switch, 630 Amps	Set	2	
65	33 KV CT PT set, 150/5 Amps	Set	4	
66	Metering cabinet	No.	4	
67	Control Cable , 10 cr.2.5 sq. mm	Mtr.	110	
68	Control Cable , 4 cr.2.5 sq. mm	Mtr.	230	
69	Horizontal boring 350 sq. mm	Mtr.	475	
70	Grouting Steel pole	No.	691	
71	Grouting of stay	No.	170	
72	Isolator fencing	Job	3	
73	Isolator foundation	Job	4	
74	RCC Foundation	Job	3	
75	RCC Foundation for VCB	Job	1	
76	RCC Foundation for LA	Job	3	
77	Installation of earthing system with MS Flat50x10 mm & 25x6 mm , GI pipe 50 mm dia 3mtr. Long	Sq. m	70	
78	Switch yard gravelling	Sq. m	70	