



ASSAM POWER DISTRIBUTION COMPANY LIMITED.

OFFICE OF THE CHIEF GENERAL MANAGER (D),

(LOWER ASSAM REGION)

CIN: U40109AS2003SGC007242

No. CGM (D&S) /APDCL /LAR/ Bongaigaon Medical College /2025-26/ **28**

Date: **28/05/2024**

To

M/s U.K. Enterprise,
Dr. R.P. Road, Dispur, Guwahati-781006

Sub: Work Order Construction of 33 kV Dedicated Medical College Feeder from 132/33 kV Dhaligaon GSS to the premises of the Bongaigaon Medical College, Majgaon and associated works under Bongaigaon ESD-I under Deposit Work Scheme on Full Turnkey Mode.

Ref: NIT No. CGM (D&S) /APDCL /LAR/ Bongaigaon Medical College /2025-26/03 date: 16.12.2025.

Dear Sir(s),

With reference to the above, we are pleased to offer the following works for execution as per rates, specifications and terms & conditions stipulated below on **“Full Turnkey Mode”** under **“Deposit Work Scheme”**.

Name of Work: Construction of 33 kV Dedicated Medical College Feeder from 132/33 kV Dhaligaon GSS to the premises of the Bongaigaon Medical College, Majgaon and associated works under Bongaigaon ESD-I under Deposit Work Scheme on Full Turnkey Mode.

1.0 Scheme of Work: “Deposit Work”.

Completion period: 365 (Three Hundred Sixty Five) days from the date of issuance of LOA.

Detail work parameters, Terms & Conditions: As declared in the Bid documents of NIT No. CGM (D&S) /APDCL /LAR/ Bongaigaon Medical College /2025-26/03 date: 16.12.2025.

2.0 Total Value of the Work: The total value of the work is **Rs. 15,43,26,670.76 (Rupees Fifteen Crore Forty Three Lakh Twenty Six Thousand Six Hundred Seventy and Seventy Six Paise Only)** inclusive of all taxes and duties.

3.0 Rates of work: The schedule of item wise rates of various works to be executed under the scheme is enclosed as **Annexure-I**. The rates are FIRM in all respects.

4.0 Scope of work:

- 4.1 Procurement and supply of materials as per given schedule required for the work.
- 4.2 **Items mentioned in BOQ may change from time to time as per requirement of work.**
- 4.3 Site unloading, storage and handling of all materials supplied by the vendor including watch and ward for safe custody.
- 4.4 Layout survey and finalization of Layout jointly with concerned field office and the consumer or his representative.
- 4.5 Clearance of jungle as per requirement of the I. E. Rules / conforming to the specification.
- 4.6 Site fabrication work as per requirement.

Page: 1 of 9

Office: Bijulee Bhawan, 5th Floor, Paltanbazar, Guwahati-781001, Ph/Fax: 0361-2739509

Email: cgmlarapdcl@gmail.com/ cgm.lar@apdcl.org Website: www.apdcl.org



ASSAM POWER DISTRIBUTION COMPANY LIMITED.

OFFICE OF THE CHIEF GENERAL MANAGER (D),

(LOWER ASSAM REGION)

CIN: U40109AS2003SGC007242

- 4.7 All the GTPs, Test Certificates and Drawings are to be submitted in triplicate to the office of the undersigned for approval.
- 4.8 Facilitating physical inspection by concerned officials of APDCL for all the materials supplied by the Vendor & obtaining approval, dispatch clearance from the CGM (D&S), APDCL (LAR) before installation. Guarantee certificates of items supplied are to be submitted to the CGM (D&S), APDCL.
- 4.9 Monthly Progress Report is to be submitted to the CGM (D&S), APDCL (LAR) through the concerned CEO, APDCL in the prescribed format.
- 4.10 Erection, Testing and Commissioning of all equipments/materials supplied / installed, dismantling of the lines & Sub-stations & making carriage of the dismantled materials to the departmental store at the field office/ establishment inclusive of loading / unloading as directed by the concerned field officer of APDCL.
- Above all, the scope of work of the Contractor will include all Items and facilities as may be necessary to complete the work as per the approved parameters as a binding requirement. The contractor shall obtain all statutory approvals and clearances from the statutory authorities before charging the system (line, Substation etc.) at their own cost*
- 4.11 The Contractor will prepare the bills for supply and erection on the basis of actual works done.
- 4.12 The contractor shall facilitate verification of the quality and quantity of the materials to be erected at site store before erection by the concerned AGM. They will ensure that the quality of the materials conform to the approved GTP/drawings.
- 4.13 To take active part in resolving RoW issues in consultation with APDCL field engineers and with necessary support from the consumer or representative.

5.0 Construction Standards:

- 5.1 All equipment/materials supplied shall conform to the requirement of relevant ISS (BIS) as specified by APDCL in the Bid Document.
- 5.2 All materials supplied shall be erected/protected/camouflaged/weather-proofed as per approved standard practice.
- 5.3 Electrical equipment like LA, switches etc. should be properly earthed and should be maintained with adequate clearance between charged points and charged point to earth point as per relevant ISS (wherever required) as per IE Rules.

6.0 Service from APDCL:

The following responsibilities for APDCL officials are defined in connection with the TURN-KEY contract to ensure effective and smooth implementation: -

- 6.1 To conduct joint survey with contractors to finalize the alignment/layout of the electrical line/sub-station etc. within approved parameters.
- 6.2 Concerned CEO/AGM will approve the alignment of proposed line, prepared by the contractor on the basis of joint survey, within three days from the date of submission of the same by the contractor.
- 6.3 To liaison with the consumer or his representative to resolve RoW issues with active participation of the contractor.

Page: 2 of 9

Office: Bijulee Bhawan, 5th Floor, Paltanbazar, Guwahati-781001, Ph/Fax: 0361-2739509

Email: cgmlarapdcl@gmail.com / cgm.lar@apdcl.org Website: www.apdcl.org



ASSAM POWER DISTRIBUTION COMPANY LIMITED.

OFFICE OF THE CHIEF GENERAL MANAGER (D),

(LOWER ASSAM REGION)

CIN: U40109AS2003SGC007242

- 6.4 On receipt of materials, the concerned AGM of Electrical Division shall verify the *quality and quantity* of materials at site. Also before commissioning of the line/substation, concerned APDCL officials should ensure that the materials, which are being utilized in the construction, strictly conform to required specification and approved GTP & drawing.
- 6.5 To arrange shut-down from APDCL's charged line and / or sub-station from the concerned authority after observing all necessary formalities as per program fixed in consultation with the contractor to facilitate construction work. In this process, power interruption should be as minimum as practicable which however should in no way affect the progress of new work.
- 6.6 APDCL's concerned field officials shall arrange Work Completion Certificate as per the prescribed format.
- 6.7 APDCL field officials will supervise the work regularly and shall ensure the work quality as per standard specifications. Any deviation if observed shall be rectified immediately by the contractor
- 6.8 To keep in safe custody all Test Certificates / Guarantee Certificates submitted by the Vendors against various materials supplied by them. Those certificates will be necessary for claiming replacement as and when required.

7.0 Tools & Plants:

The Contractor shall arrange all required tools and plants on his own. APDCL in no way shall extend any support in this regard.

8.0 Period of Completion: 365 (Three Hundred Sixty Five) days from the date of issuance of LOA.

9.0 Inspection and testing:

All the equipments/materials to be supplied and erected, shall be tested/inspected at manufacturer's work by authorized officer(s) of APDCL before dispatching them to work site. The contractor shall intimate CGM (D), APDCL (LAR) at least 15 (fifteen) days in advance the date of inspection of materials at manufacturer's works. The materials should be dispatched to site only after receipt of dispatch clearance to be issued by the CGM (D)/APDCL's Inspecting Officer after satisfactory testing of the same.

10.0 Verification and site Inspection of materials:

The contractor shall bring the materials/equipment to their site store after approval of the same by APDCL's inspecting officer in factory testing and intimate the concerned CEO for verification of the same. The CEO shall make arrangement for site inspection of the materials by the concerned AGM of APDCL and after proper verification of the same as per approved GTP/ drawing shall issue Materials Verification and Inspection Certificate as per prescribed format. At the time of verification of materials at contractor's store, the dispatch documents (Heavy Vehicle /Railway receipt/challan etc. in original) for the materials offered for inspection shall be produced by the contractor.

Page: 3 of 9

Office: Bijulee Bhawan, 5th Floor, Paltanbazar, Guwahati-781001, Ph/Fax: 0361-2739509

Email: cgmlarapdcl@gmail.com/ cgm.lar@apdcl.org Website: www.apdcl.org



ASSAM POWER DISTRIBUTION COMPANY LIMITED.

OFFICE OF THE CHIEF GENERAL MANAGER (D),

(LOWER ASSAM REGION)

CIN: U40109AS2003SGC007242

Terms of Payment:

11.1. During the continuance of the Contract, maximum 2(two) nos. of Progressive bills shall be entertained. The progressive payments shall be made for the actual volume of work including supply as well as erection of the materials under the following conditions:

11.2. **1st Progressive Bill:** - 80% (eighty percent) payment against 1st progressive bill shall be released retaining the balance 20% (twenty percent) amount, subject to the condition that minimum 40% (forty percent) BOQ materials of the LOA have been erected successfully. The bill shall be supplemented by the following documents, satisfactory verification and acceptance of which shall make the Contractor eligible for receipt of payment against the progressive bill:

- i) Unconditional acceptance of the Letter of Award (LOA) and signing of Contract Agreement by the Contractor.
- ii) Submission of an unconditional and irrevocable Bank Guarantee for 10% (ten percent) of the Contract price in pursuant terms and condition of the bid.
- iii) Submission of GST invoice/GST E-invoice (if applicable) consisting the GSTIN & PAN No. of the Contractor as well as APDCL must be mentioned in the Bill in printed form along with the Name of Work, LOA No., HSN/SAC code etc.
- iv) **In consonance to the Office order no. APDCL/GST/OTHERS/669/02 Dtd. 04-09-2021, the contractor shall mandatorily submit the copy of GSTR1 (respective pages only - B2B Receiver wise summary, B2B Invoice Summary), wherein their invoice wise details shall be available and GSTR 3B filed.**
The payment shall be suspended in the event of non-compliance of the said office order.
- v) Copy of the Material Inspection & Clearance Certificate (MICC) and Material Receipt and Handing Over Voucher (MRHOV) duly signed by the concerned consignee location and duly countersigned by the CEO of the concerned Electrical Circle.
- vi) Manufacturer's copy of the Delivery Challan.
- vii) Manufacturer's Warranty Certificate for the materials under bill submission.
- viii) Photographic evidences of the supplied materials duly signed by the concerned consignee location and duly countersigned by the CEO of the Electrical Circle.
- ix) Submission of Physical Progress Report as per the proforma provided along with the LOA duly signed by the concerned consignee location and duly countersigned by the CEO of the Electrical Circle.
- x) Upload the photographic evidence of actual physical progress through APDCL Work Master Application for relevant BOQ of the materials. The information received through this app will be verified with the supply and erected quantities before releasing of the bills.

11.3 **2nd Progressive Bill:** - 80% (eighty percent) payment against the 2nd progressive bill shall be released retaining the balance 20% (twenty percent) amount, subject to the condition that minimum 40% (forty percent) BOQ materials of the LOA have been erected successfully in addition to the 40% materials erected earlier against 1st progressive bill. The documents indicated against point 11.2 above (SI No. i to x) shall also require to be submitted along with the bill, satisfactory verification and acceptance of which shall make the Contractor eligible for receipt of payment against the progressive bill.

11.4 **3rd and Final Bill:** - 100% (hundred percent) payment against the 3rd and final bill shall be released along with the 20% (twenty percent) retention amount of respective 1st and 2nd Progressive Bills after successful completion and commissioning of the project subject to submission, acceptance and validity of the Performance Bank Guarantee in accordance to the clause of the ITB. The documents indicated against point 11.2 above (SI No. i to x) shall also require to be submitted along with the bill, satisfactory verification and acceptance of which shall make the Contractor eligible for receipt of final payment.

Page: 4 of 9

Office: Bijulee Bhawan, 5th Floor, Paltanbazar, Guwahati-781001, Ph/Fax: 0361-2739509

Email: cgmrapdcl@gmail.com/ cgm.lar@apdcl.org Website: www.apdcl.org



ASSAM POWER DISTRIBUTION COMPANY LIMITED.

OFFICE OF THE CHIEF GENERAL MANAGER (D),

(LOWER ASSAM REGION)

CIN: U40109AS2003SGC007242

11.5 All the aforesaid bills after due verification by the concerned Sub-Divisional Engineer, 100% of the bill passed by the concerned Electrical Division and countersigned by the concerned Chief Executive Officer (CEO) of the Electrical Circle, shall be placed before the **CGM (LAR), APDCL** for payment.

11.6 All the material and billing related transactions must be executed through ERP system only. In this context, the respective consignee locations are requested to undertake necessary steps to perform the goods receipt/service acceptance related transactions against the PO/WO number. No supply/erection bills shall be processed for payment unless the necessary transactions in ERP are performed by the consignee locations.

11.7 The right of the contractor/supplier to have payment or reimbursement of any cost for execution of works/supply of materials as the case may be, against this order will be forfeited or deemed to have been relinquished if the claim for it is not referred to the appropriate authority within 6 (Six) months from the date of completion or deemed completion as per clause of Company's GCSE.

11.8 The Payment shall be made **subject to availability of Fund.**

12.0 Security deposit and agreement:

Security deposit in the form of Bank Guarantee issued by any Nationalized Bank or scheduled bank of RBI (situated in Assam) in Company's standard proforma on non-judicial stamp paper for an amount equal to 10% of the contract value as per NIT is to be deposited at the time of execution of agreement in favour of "The CGM (F&A), APDCL, Guwahati-1" to the CGM (D&S), APDCL (LAR) as per Company's terms and conditions, valid for a period of 60 (sixty) days beyond the stipulated date of completion of the project as per LOA. The security deposit is liable to be forfeited in case of non-execution of contract / work order. The security deposit will be released on successful commissioning and testing of the materials ordered on submission of contract performance B/G.

- a. If the contractor fails or neglects to perform any of his obligations under the contract within the guarantee period, APDCL shall have the right to forfeit the BG submitted against performance either in full or in part at its absolute discretion. No interest shall be payable on such deposits.
- b. All Bank 'Guarantees (BG) submitted along with the bid or to be submitted later, should be from those branches of nationalized or scheduled Bank of RBI having their regional offices in Assam or at least a branch office at Guwahati (In case of those, whose regional office is not located in the state of Assam) with a certificate from the Bank to the effect that the verification or any confirmation in regard to the BG issued by the bank can be taken up with the Branch office at Guwahati.

13.0 Performance Bank Guarantee

- a. Performance Bank Guarantee from any Nationalized Bank in Company's/ Board's Standard Proforma, with a **validity of 20 (18 + 2) (Eighteen + Two) months** from the date of successful commissioning of the work, for an amount equal to **10%** of the total value of **work executed** shall have to be furnished by the contractor to the CGM (D&S), APDCL, LAR in favour of the **CGM (F &A), APDCL before** releasing the final payment.

Page: 5 of 9

Office: Bijulee Bhawan, 5th Floor, Paltanbazar, Guwahati-781001, Ph/Fax: 0361-2739509

Email: cgmlarapdcl@gmail.com/ cgmlar@apdcl.org Website: www.apdcl.org



ASSAM POWER DISTRIBUTION COMPANY LIMITED.

OFFICE OF THE CHIEF GENERAL MANAGER (D),

(LOWER ASSAM REGION)

CIN: U40109AS2003SGC007242

- b. If the contractor fails or neglects to perform any of his obligations under the contract within the guarantee period, APDCL shall have the right to forfeit the BG submitted against performance either in full or in part at its absolute discretion.
- c. No interest shall be payable on such deposits

14.0 Income Tax: Income Tax will be deducted at source as per rules.

15.0 Taxes and Duties:

The approved package value is inclusive of applicable taxes and duties. Taxes & duties under the subject contract shall be governed by the provisions of prevailing Tax Act of State & Central Govt. The statutory deduction of taxes and duties (wherever applicable), related to these works shall be done by APDCL. TDS, so deducted, shall be deposited with the relevant tax authorities and TDS certificate shall be issued by APDCL using his Permanent account number and TDS account number for filing necessary returns.

16.0 Liquidated Damage

The period of completion as mentioned above should strictly be adhered to. Any delay beyond the specified period (barring *Force Majeure* conditions) will attract Liquidated Damage as per APDCL's General Conditions of supply and erection (GCSE).

17.0 Guarantees:

Equipment / Materials Guarantee: Equipment & materials installed shall be guaranteed individually and also for integrated operations for a period of 18 (eighteen) months from the date of commissioning

In case of detection of any defect in individual equipment or in the system as a whole, the same shall be replaced / corrected by the contractor free of cost within 15(fifteen) days of intimation by the APDCL's representative in writing.

18.0 Warranty from manufacturer shall be produced along with manufacturer's Test Certificate for all equipment & materials before release of final bill.

19.0 Dispute Resolution:

- (i) In case of any dispute, controversy or claim arising out of or relating to this contract/ agreement, the matter shall be settled amicably between both the parties by serving a notice from either party. The matter shall be settled within a period of thirty (30) days from the date of receipt of the said notice.
- (ii) In case of non- receipt of any response of the notice as stated in clause (i), then, the dispute, controversy or claim arising out of or relating to this contract/ agreement or the breach, termination or invalidity thereof shall be settled by arbitration in accordance with the provisions of the Arbitration and Conciliation Act, 1996 *as may be amended from time to time*.
- (iii) *The seat and venue of arbitration shall be Guwahati, Assam. The proceedings shall be undertaken in English. The arbitration award shall be final and binding on the parties.*



ASSAM POWER DISTRIBUTION COMPANY LIMITED.

OFFICE OF THE CHIEF GENERAL MANAGER (D),

(LOWER ASSAM REGION)

CIN: U40109AS2003SGC007242

20.0 Jurisdiction of Court:

The Gauhati High Court shall have exclusive jurisdiction to adjudicate any dispute arising under or in connection with this Agreement.

21.0 Contractor's default:

- a. If the Contractor neglects to execute the Works with due diligence and expertise or refuses to comply with any reasonable order given to him, in the Contract by the Engineer in connection with the works or shall contravene the provisions of the Contract, the owner may give notice in writing to the contractor to make good the failure, neglect or contravention complained of. Should the contractor fail to comply with the notice within thirty (30) days from the date of serving the notice, then and in such case the Owner shall be at liberty to employ other workmen and forthwith execute such part of the works as the Contractor, may have neglected to do or if the owner shall think fit, without prejudice to any other right he may have under the Contract to take the work wholly or in part out of the contractor's hands and re-contract with any other person or persons to complete the works or any part thereof and in that event the Owner shall have free use of all Contractor's equipment that may have been at the time on the site in connection with the works without being responsible to the Contractor for fair wear and tear thereof and to the exclusion of any right of the contractor over the same, and the Owner shall be entitled to retain and apply any balance which may otherwise be due on the Contract by him to the contractor, or such part thereof as may be necessary, to the payment of the cost of executing the said part of the work or of completing the Works as the case may be. If the cost of completing of Works or executing a part thereof as aforesaid shall exceed the balance due to the contractor, the contractor shall pay such excess. Such payment of excess amount shall be independent of the liquidated damages for delay which the contractor shall have to pay if the completion of works is delayed.
- b. In addition, such action by the Owner as aforesaid shall not relieve the Contractor of his liability to pay liquidated damages for delay in completion of works as defined in clause no.26 of GCSE
- c. Such action by the Owner as aforesaid, the termination of the Contract under this clause shall neither entitle the contractor to reduce the value of the contract Performance Guarantee nor the time thereof. The contract Performance Guarantee shall be valid for the full value and for the full period of the contract including guarantee period.

22.0 Termination of contract on owners' initiative:

- a. The Owner reserves the right to terminate the Contract either in part or in full due to reasons other than those mentioned under clause entitled "Contractor's Default." The Owner shall in such an event give fifteen (15) days' notice in writing to the Contractor of his decision to do so.
- b. The Contractor upon receipt of such notice shall discontinue the work on the date and to the extent specified in the notice, make all reasonable efforts to obtain cancellation of all orders and contracts to the extent they are related to the work terminated and terms satisfactory to the Owner, stop all further sub-contracting or purchasing activity related to the work terminated, and assist the Owner in maintenance, protection, and disposition of the Works acquired under the Contract by the Owner.
- c. In the event of such a termination, the Contractor shall be paid compensation, equitable and reasonable, dictated by the circumstances prevalent at the time of termination.

Page: 7 of 9



ASSAM POWER DISTRIBUTION COMPANY LIMITED.

OFFICE OF THE CHIEF GENERAL MANAGER (D),

(LOWER ASSAM REGION)

CIN: U40109AS2003SGC007242

d. If the Contractor is an individual or a proprietary concern and the individual or the proprietor dies and if the contractor is a partnership concern and one of the partners dies then unless the Owner is satisfied that the legal representatives of the individual contractor or of the proprietor of propriety concern and in the case of partnership, the surviving partners, are capable of carrying out and completing the Contract, the Owner shall be entitled to cancel the Contract as to its uncompleted part without being in any way liable to payment of any compensation to the estate of deceased Contractor and/or to surviving partners of the contractor's firm on account of the cancellation of the contract. The decision of the owner that the legal representatives of the deceased contractor or surviving partners of the contractor's firm cannot carry out and complete the contract shall be final and binding on the parties. In the event of such cancellation, the Owner shall not hold the estate of the deceased Contractor and/or the surviving partner of the Contractor's firm liable to damages for not completing the Contract.

23.0 Frustration of contract:

a. In the event of frustration of the contract of supervening impossibility in items of Section 56 of the Indian Contract Act, parties shall be absolved of their responsibility to perform the balance portion of the contract.

b. In the event of non-availability or suspension of funds for any reasons whatsoever (except for reason of willful or flagrant breach by the Owner and/or contractor) then the works under the contract shall be suspended. Furthermore, if the Owner is unable to make satisfactory alternative arrangements for financing to the contractor in accordance with the terms of the Contract within three months of the event, the parties hereto shall be relieved from carrying out further obligations under the Contract treating it as frustration of the Contract. In the event Performance Bank Guarantee, the parties shall mutually discuss to arrive at reasonable on all issues including amounts due to either party for the work already done on "Quantum Merit" basis which shall be determined by mutual agreement between the parties.

24.0 Environmental Considerations:

While carrying out the assignment, no damage to the environment will be caused by the contractor. If so done, the contractor will have to compensate the same to the satisfaction of the concerned authority.

25.0 Insurance:

The contractor shall take necessary coverage under LIC / GIC etc. for his working personnel and the Goods in store as well as in transit and constructed sub-stations equipments till the date of handing over to APDCL. APDCL will not be responsible for any compensation, replenishment, damage, theft etc. as may be caused due to negligent working, lack of co-ordination with Govt. / non-Govt. / local authority by the contractor or by his personnel deputed for the work.

26.0 Labour Laws & Regulations: The contractor shall employ personnel observing provision of labour laws. A copy of the current labour license is to be submitted.

Terms and conditions, which are not specified, herein above will be governed by Company's General Conditions of supply and erection in force. Any clarification if required for proper understanding of clauses of this Work Order the relevant section of the bid documents shall prevail and binding.



ASSAM POWER DISTRIBUTION COMPANY LIMITED.

OFFICE OF THE CHIEF GENERAL MANAGER (D),

(LOWER ASSAM REGION)

CIN: U40109AS2003SGC007242

Please attend this office to sign the Contract Agreement within 7 (Seven) days from the date of issuance of the work order after deposit of the requisite security amount in the form of BG. This date of agreement is non-negotiable.

Encl: as stated.

Prepared by


AGM (LAR)

Checked by


DGM (F&A)


DGM (LAR)

Yours faithfully,


Chief General Manager (D&S),
APDCL (LAR)

Memo No. CGM (D&S) /APDCL /LAR/ Bongaigaon Medical College /2025-26/
Copy to:

Date:

1. The CGM (F&A), APDCL, Bijulee Bhawan for information. This has reference to the **approval of TPC-I vide resolution No. 370/25-26 dated 12.03.2026.**
2. The General Manager, Bongaigaon Zone, APDCL, LAR, Bongaigaon for information.
3. The CEO, Bongaigaon Electrical Circle, APDC, LAR, Bongaigaon for information.
4. The AGM, Bongaigaon Electrical Division, APDCL, LAR, Bongaigaon for information.
5. The SDE, Bongaigaon Electrical Sub-Division-I, APDCL, LAR, Bongaigaon for information.


Chief General Manager (D&S)
APDCL (LAR).

Page: 9 of 9

Tender Inviting Authority: CGM(D&S),LAR,APDCL

- Name of Work: Construction of 33 KV Dedicated Medical College Feeder from 132/33 KV Dhaligaon GSS to the premises of the Bongalgaon Medical College, Malgaon and associated works under Bongalgaon ESD-1 under Deposit Work Scheme on Full Turnkey Mode

Contract No:

M/s. U K ENTERPRISE		PRICE SCHEDULE SUMMARY																		
Name of the Bidder/ Bidding Firm / Company :		(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)																		
NUMBER #	Sl. No.	TEXT #	Item Description	NUMBER #	Quantity	TEXT #	Units	NUMBER #	Unit Rate for Supply of material (Inclusive of All Applicable Taxes and Duties) (In Rs.)	NUMBER	Total Amount for Supply	NUMBER	Unit Rate for Erection of material (Inclusive of All Applicable Taxes and Duties) (In Rs.)	NUMBER #	Total Amount for Erection of material	NUMBER #	Total Amount (Supply + Erection) (Inclusive of All Applicable Taxes and Duties) (In Rs.)	TOTAL AMOUNT In Words	TEXT #	
1	1.01	2	Construction of 33 KV Dedicated Medical College Feeder from 132/33 KV Dhaligaon GSS to the premises of the Bongalgaon Medical College situated at Malgaon, Bongalgaon and construction of 11 KV & LT Composite lines for ROW of 33 KV Bongalgaon Medical College Dedicated Feeder and installation of HT metering system (Billing & Check Meter) (refer Annexure-1) Itemwise price should be filled in strictly as per the detailed Bill of Quantities at respective referred Annexure.		4	5	No	7	103180877.96	16	103180877.96	17	10902599.44	11	10902599.44	12	114083477.40	13	INR Eleven Crore Forty Lakh Eighty Three Thousand Four Hundred & Seventy Seven and Paise Four Zero Only	
	1.02		Construction of 33 KV UG Railway Track Crossing for 33 KV Dedicated feeder at Bhakarvita (near Ambedkar Hall to Track Depot NF Railway) in between KM 252/3 and 252/4 of Railway Track (refer Annexure-2) Itemwise price should be filled in strictly as per the detailed Bill of Quantities at respective referred Annexure.		1.00		No		2943460.44		2943460.44		272331.32		272331.32		3215791.76		INR Thirty Two Lakh Fifteen Thousand Seven Hundred & Ninety One and Paise Seven Six Only	
	1.03		Construction of 33 KV Spur line from 33/11 KV Birjhora Sub-Station to 33/11 KV Bongalgaon Medical College Feeder at Barpara near Arogya Hospital gate as alternate stand by source of power from 33/11 KV Birjhora Sub-Station and Construction of 11 KV & LT Composite lines for ROW of 33 KV Line (refer Annexure-3) Itemwise price should be filled in strictly as per the detailed Bill of Quantities at respective referred Annexure.		1.00		No		31088412.16		31088412.16		3659406.18		3659406.18		34747818.34		INR Three Crore Forty Seven Lakh Forty Seven Thousand Eight Hundred & Eighteen and Paise Three Four Only	
	1.04		Construction of Terminal Bay at the 33/11 KV Birjhora Sub-Station for 33 KV feeder from 33/11 KV Birjhora Sub-Station to 33 KV Bongalgaon Medical College Feeder (near Arogya Hospital Gate) (refer Annexure-4) Itemwise price should be filled in strictly as per the detailed Bill of Quantities at respective referred Annexure.		1.00		No		1787641.00		1787641.00		146756.86		146756.86		1934397.86		INR Nineteen Lakh Thirty Four Thousand Three Hundred & Ninety Seven and Paise Eight Six Only	
	1.05		Dismantling of 11 KV & LT lines of 11 KV Bageswari feeder, 11 KV Bongalgaon Civil Hospital Feeder and 11 KV Dhaligaon feeder under BESD-II for ROW of 33 KV Dedicated Feeder from Dhaligaon GSS to Bongalgaon Medical College at Malgaon, Bongalgaon and 33/11 KV Birjhora DSS to Bongalgaon Medical Hospital feeder at Barpara, or providing 33 KV power supply to the premises of 'New Medical College & Hospital, Malgaon' (refer Annexure-5) Itemwise price should be filled in strictly as per the detailed Bill of Quantities at respective referred Annexure.		1.00		No		0.00		0.00		345185.40		345185.40		345185.40		INR Three Lakh Forty Five Thousand One Hundred & Eighty Five and Paise Four Zero Only	
Total In Figures																	139000391.56	15326279.20	154326670.76	INR Fifteen Crore Forty Three Lakh Twenty Six Thousand Six Hundred & Seventy and Paise Seven Six Only
Quoted Rate in Words		INR Fifteen Crore Forty Three Lakh Twenty Six Thousand Six Hundred & Seventy and Paise Seven Six Only																		

Item Wise BoQ

Tender Inviting Authority: Name of Work: Construction of 33 KV Dedicated Medical College Feeder from 132/33 KV Dhaligaon GSS to the premises of the Bongalgaon Medical College situated at Majgaon, Bongalgaon and construction of 11 KV & LT Composite lines for ROW of 33 KV Bongalgaon Medical College
Dedicated Feeder and Installation of HT metering system (Billing & Check Meter)
Contract No:

Name of the Bidder/ Bidding Firm / Company :		M/s. U K ENTERPRISE																
ANNEXURE 1																		
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	TEXT	TEXT	TEXT	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Unit Rate for Supply of material (in Rs.)	CGST on Supply of material @9% Rs. P	SGST on Supply of material @9% Rs. P	Total Amount for Supply of material inclusive of GST	Unit Rate for Erection of material (incl. testing and commissioning) (in Rs.)	CGST on Erection of material @9% Rs. P	SGST on Erection of material @9% Rs. P	Total Amount for Erection of material inclusive of GST	Total Amount (Supply + Erection) (Inclusive of All Applicable Taxes and Duties) (in Rs.)	TOTAL AMOUNT In Words					
1	2	4	5	13	14	15	16	17	18	19	53	54	55					
1	GI Steel Tubular Pole SP-75	489	No.	52000.00	4680.00	4680.00	30005040.00	6240.00	561.60	561.60	3600604.80	33605644.80	INR Three Crore Thirty Six Lakh Five Thousand Six Hundred & Forty Four and Paise Eighty Only					
2	GI Steel Tubular Pole SP-80	12	No.	54000.00	4860.00	4860.00	764640.00	3780.00	340.20	340.20	53524.80	818164.80	INR Eight Lakh Eighteen Thousand One Hundred & Sixty Four and Paise Eighty Only					
3	33kV Grade Isolator, TPGO-DCBR without earth switch and GI Mounting Structure, 800 Amps	2	Set	70000.00	6300.00	6300.00	165200.00	4900.00	441.00	441.00	11564.00	176764.00	INR One Lakh Seventy Six Thousand Seven Hundred & Sixty Four Only					
4	33kV Lightning Arrestor, 10KA, (Line type)	6	Set	25000.00	2250.00	2250.00	177000.00	1750.00	157.50	157.50	12390.00	189390.00	INR One Lakh Eighty Nine Thousand Three Hundred & Ninety Only					
5	Polymeric Pin Insulator (FRP 34mm)	1328	No.	790.00	71.10	71.10	1237961.60	55.30	4.98	4.98	86665.28	1324626.88	INR Thirteen Lakh Twenty Four Thousand Six Hundred & Twenty Six and Paise Eighty Eight Only					
6	GI Nuts & Bolts with Washers (assorted)	1310	Kg.	210.00	18.90	18.90	324618.00	14.70	1.32	1.32	22715.40	347333.40	INR Three Lakh Forty Seven Thousand Three Hundred & Thirty Three and Paise Forty Only					
7	GI Pole Clamp with GI Flat 50x6mm	2550	No.	210.00	18.90	18.90	631890.00	14.70	1.32	1.32	44217.00	676107.00	INR Six Lakh Seventy Six Thousand One Hundred & Seven Only					
8	GI Channel Cross-Arm (100x50x6x3200mm)	369	No.	2500.00	225.00	225.00	1088550.00	175.00	15.75	15.75	76198.50	1164748.50	INR Eleven Lakh Sixty Four Thousand Seven Hundred & Forty Eight and Paise Fifty Only					
9	GI Angle (50x50x6mm) for Cross-Bracing	2394	Mtr.	370.00	33.30	33.30	1045220.40	25.90	2.33	2.33	73160.64	1118381.04	INR Eleven Lakh Eighteen Thousand Three Hundred & Eighty One and Paise Four Only					
10	GI 33kV V-Cross Arm with Channel size (100x50x6) mm	360	No.	2100.00	189.00	189.00	892080.00	147.00	13.23	13.23	62445.60	954525.60	INR Nine Lakh Fifty Four Thousand Five Hundred & Twenty Five and Paise Sixty Only					
11	GI Top Cleat of Channel 100x50x6x350mm	360	No.	360.00	32.40	32.40	152928.00	25.20	2.27	2.27	10706.40	163634.40	INR One Lakh Sixty Three Thousand Six Hundred & Thirty Four and Paise Forty Only					
12	GI Angle (50x50x6mm) for Guarding	1608	Mtr.	370.00	33.30	33.30	702052.80	25.90	2.33	2.33	49140.48	751193.28	INR Seven Lakh Fifty One Thousand One Hundred & Ninety Three and Paise Twenty Eight Only					
13	GI Tye Angle (50x50x6x1000mm)	1152	No.	370.00	33.30	33.30	502963.20	25.90	2.33	2.33	35205.12	538168.32	INR Five Lakh Thirty Eight Thousand One Hundred & Sixty Eight and Paise Thirty Two Only					
14	GI Jam Clamp with GI Angle 50x50x6mm	112	Mtr.	370.00	33.30	33.30	48899.20	25.90	2.33	2.33	3422.72	52321.92	INR Fifty Two Thousand Three Hundred & Twenty One and Paise Ninety Two Only					
15	33kV 1-Core x 241sqmm AAAC Triple Extruded Covered Conductor	44750	Mtr.	790.00	71.10	71.10	41715950.00	84.00	7.56	7.56	4435620.00	46151570.00	INR Four Crore Sixty One Lakh Fifty One Thousand Five Hundred & Seventy Only					
16	33kV Mid-span Jointing Kit for 33kV 1-Core x 241sqmm AAAC Covered Conductor	95	No.	1800.00	162.00	162.00	201780.00	126.00	11.34	11.34	14124.60	215904.60	INR Two Lakh Fifteen Thousand Nine Hundred & Four and Paise Sixty Only					
17	33kV Cable Termination Kit for 1-Core x 241sqmm AAAC Covered Conductor	525	No.	1800.00	162.00	162.00	1115100.00	126.00	11.34	11.34	78057.00	1193157.00	INR Eleven Lakh Ninety Three Thousand One Hundred & Fifty Seven Only					

[Handwritten Signature]

[Handwritten Mark]

[Handwritten Mark]

[Handwritten Mark]

18	33kV Tension Insulator for 1-Core x 241sqmm AAAC Covered Conductor	525	No.	790.00	71.10	71.10	489405.00	55.30	4.88	4.98	34261.50	523666.60	INR Five Lakh Twenty Three Thousand Six Hundred & Sixty Six and Paise Fifty Only
19	33kV Tension Hardware for 1-Core x 241sqmm AAAC Covered Conductor	525	No.	1600.00	144.00	144.00	991200.00	112.00	10.08	10.08	69384.00	1060584.00	INR Ten Lakh Sixty Thousand Five Hundred & Eighty Four Only
20	33kV Cable Tie for 1-Core x 241sqmm AAAC Covered Conductor	1325	No.	1000.00	90.00	90.00	1563500.00	70.00	6.30	6.30	109445.00	1672945.00	INR Sixteen Lakh Seventy Two Thousand Nine Hundred & Forty Five Only
21	33kV Danger Plate	491	No.	100.00	9.00	9.00	57938.00	7.00	0.63	0.63	4055.66	61993.66	INR Sixty One Thousand Nine Hundred & Ninety Three and Paise Sixty Six Only
22	HT Stay Set	92	Set	700.00	63.00	63.00	75992.00	49.00	4.41	4.41	5319.44	81311.44	INR Eighty One Thousand Three Hundred & Eleven and Paise Forty Only
23	33kV Grade Guy Insulator (Porcelain)	92	No.	50.00	4.50	4.50	5428.00	3.50	0.32	0.32	380.88	5808.88	INR Five Thousand Eight Hundred & Eight and Paise Eighty Eight Only
24	GI Stay Wire, 7/10 SWG	680	Kg.	64.00	5.76	5.76	51353.60	4.48	0.40	0.40	3590.40	54944.00	INR Fifty Four Thousand Nine Hundred & Forty Four Only
25	GI Wire 8 SWG for Guarding & Earthing	16050	Kg.	64.00	5.76	5.76	1212096.00	4.48	0.40	0.40	84744.00	1296840.00	INR Twelve Lakh Ninety Six Thousand Eight Hundred & Forty Only
26	GI Barbed Wire	1098	Kg.	64.00	5.76	5.76	82920.96	4.48	0.40	0.40	5797.44	88718.40	INR Eighty Eight Thousand Seven Hundred & Eighteen and Paise Forty Only
27	GI Earth Pipe 50mm. dia., 3mtr. length	541	No.	1800.00	162.00	162.00	1149084.00	126.00	11.34	11.34	80435.88	1229519.88	INR Twelve Lakh Twenty Nine Thousand Five Hundred & Nineteen and Paise Eighty Eight Only
28	11kV Pin Insulator Polymeric	970	No.	500.00	45.00	45.00	572300.00	35.00	3.15	3.15	40061.00	612361.00	INR Six Lakh Twelve Thousand Three Hundred & Sixty One Only
29	ACSR Raccoon Conductor	29.23	KM	81000.00	7290.00	7290.00	2793803.40	6670.00	610.30	510.30	195566.24	2989369.64	INR Twenty Nine Lakh Eighty Nine Thousand Three Hundred & Sixty Nine and Paise Sixty Four Only
30	1kV Grade Disc Insulator (Polymer) 70kN (T&C Type)	324	No.	500.00	45.00	45.00	191160.00	35.00	3.15	3.15	13381.20	204541.20	INR Two Lakh Four Thousand Five Hundred & Forty One and Paise Twenty Only
31	H/W Fittings for Raccoon	324	No.	500.00	45.00	45.00	191160.00	35.00	3.15	3.15	13381.20	204541.20	INR Two Lakh Four Thousand Five Hundred & Forty One and Paise Twenty Only
32	Tension Clamp for Raccoon	324	No.	180.00	16.20	16.20	68817.60	12.60	1.13	1.13	4814.64	73632.24	INR Seventy Three Thousand Six Hundred & Thirty Two and Paise Twenty Four Only
33	PG Clamp for Raccoon	318	No.	300.00	27.00	27.00	112572.00	21.00	1.89	1.89	7880.04	120452.04	INR One Lakh Twenty Thousand Four Hundred & Fifty Two and Paise Four Only
34	GI Channel Cross Arm (100x50x6x200mm) side bracing for 11kV Composite Line	280	No.	1800.00	162.00	162.00	594720.00	126.00	11.34	11.34	41630.40	636350.40	INR Six Lakh Thirty Six Thousand Three Hundred & Fifty and Paise Forty Only
35	33kV Grade XLPE Insulated Armoured 1-Core x 630 sqmm Cable	1800	Mtr.	1800.00	162.00	162.00	3823200.00	126.00	11.34	11.34	267624.00	4090824.00	INR Forty Lakh Ninety Thousand Eight Hundred & Twenty Four Only
36	Cable Termination Kit for 33kV Grade XLPE Insulated Armoured 1-Core x 630 sqmm Cable (Rate of 400sqmm)	30	No.	5000.00	450.00	450.00	177000.00	350.00	31.50	31.50	12390.00	189390.00	INR One Lakh Eighty Nine Thousand Three Hundred & Ninety Only
37	HDPE Pipe PE100 110mm dia. Outer dia.	210	Mtr.	500.00	45.00	45.00	123900.00	35.00	3.15	3.15	8673.00	132573.00	INR One Lakh Thirty Two Thousand Five Hundred & Seventy Three Only
38	CI Spun Pipe Class 1A type 300mm dia., 5.5Mtr. Length	60	No.	12000.00	1080.00	1080.00	849600.00	840.00	75.60	75.60	59472.00	909072.00	INR Nine Lakh Nine Thousand & Seventy Two Only
39	Bend for CI Spun Pipe	60	No.	1000.00	90.00	90.00	70800.00	70.00	6.30	6.30	4956.00	75756.00	INR Seventy Five Thousand Seven Hundred & Fifty Six Only
40	33kV GOAB switch 800Amp	6	Set	16000.00	1440.00	1440.00	113280.00	1120.00	100.80	100.80	7929.60	121209.60	INR One Lakh Twenty One Thousand Two Hundred & Nine and Paise Sixty Only
41	GI LT Angle Cross Arm (40x40x500)mm	926	No.	230.00	20.70	20.70	251316.40	16.10	1.45	1.45	17594.00	268910.40	INR Two Lakh Sixty Eight Thousand Nine Hundred & Ten and Paise Forty Only
42	LT Pin Insulator (Porcelain)	2042	No.	50.00	4.50	4.50	120478.00	3.50	0.32	0.32	8453.88	128931.88	INR One Lakh Twenty Eight Thousand Nine Hundred & Thirty One and Paise Eighty Eight Only
43	LT GI Pin	2042	No.	25.00	2.25	2.25	60239.00	1.75	0.16	0.16	4226.94	64465.94	INR Sixty Four Thousand Four Hundred & Sixty Five and Paise Ninety Four Only
44	Shackle Insulator Porcelain	516	No.	50.00	4.50	4.50	30444.00	3.50	0.32	0.32	2136.24	32580.24	INR Thirty Two Thousand Five Hundred & Eighty and Paise Twenty Four Only

45	LT GI Shackle Strap with Bolts	516	No.	25.00	2.25	2.25	15222.00	1.75	0.16	0.16	1068.12	16290.12	INR Sixteen Thousand Two Hundred & Ninety and Paise Twelve Only
46	Pole Clamp of GI Flat 50x6mm	926	No.	210.00	18.90	18.90	229462.80	14.70	1.32	1.32	16056.84	245519.64	INR Two Lakh Forty Five Thousand Five Hundred & Nineteen and Paise Sixty Four Only
47	ACSR "RABBIT" Conductor	49.9	KM	64000.00	5760.00	5760.00	3769448.00	4480.00	403.20	403.20	263791.36	4032239.36	INR Forty Lakh Thirty Two Thousand Two Hundred & Thirty Nine and Paise Thirty Six Only
48	11kV Grade XLPE Insulated Armoured 1-Core x 630 sqmm Cable	200	Mtr.	18000.00	162.00	162.00	424800.00	126.00	11.34	11.34	29736.00	454536.00	INR Four Lakh Fifty Four Thousand Five Hundred & Thirty Six Only
49	LPE CABLE JOINTING KIT 11kV OUTDOOR TYPE 1C 630 sq.mm(Rate in 400sqmm).	8	No.	4500.00	405.00	405.00	42480.00	315.00	28.35	28.35	2973.60	45453.60	INR Forty Five Thousand Four Hundred & Fifty Three and Paise Sixty Only
50	HDPE Pipe PE100 110mm dia. Outer dia.	56	Mtr.	500.00	45.00	45.00	33040.00	35.00	3.15	3.15	2312.80	35352.80	INR Thirty Five Thousand Three Hundred & Fifty Two and Paise Eighty Only
51	CI Spun Pipe Class 1A type 300mm dia., 5.5Mtr. Length	6	No.	12000.00	1080.00	1080.00	84960.00	840.00	75.60	75.60	5947.20	90907.20	INR Ninety Thousand Nine Hundred & Seven and Paise Twenty Only
52	Bend for CI Spun Pipe	6	No.	1000.00	90.00	90.00	7080.00	70.00	6.30	6.30	495.60	7575.60	INR Seven Thousand Five Hundred & Seventy Five and Paise Sixty Only
53	LIGHTNING ARRESTOR 11kV 10KA Lightning Arrestor Station Type Class 2	2	Set	5000.00	450.00	450.00	11800.00	350.00	31.50	31.50	826.00	12626.00	INR Twelve Thousand Six Hundred & Twenty Six Only
54	11kV GOAB switch 630Amp	2	Set	10000.00	900.00	900.00	23600.00	700.00	63.00	63.00	1652.00	25252.00	INR Twenty Five Thousand Two Hundred & Fifty Two Only
55	33kV Combined CT-PT Set, 150/5 A, Accuracy Class 0.2	2	Set	0.00	0.00	0.00	0.00	7000.00	630.00	630.00	16520.00	16520.00	INR Sixteen Thousand Five Hundred & Twenty Only
56	Metering Cabinet	2	No.	7000.00	630.00	630.00	16520.00	490.00	44.10	44.10	1156.40	17676.40	INR Seventeen Thousand Six Hundred & Seventy Six and Paise Forty Only
57	CONTROL CABLE, 1.1kV GRADE (COPPER), 10C x 2.5 sqmm	30	Mtr.	390.00	35.10	35.10	13806.00	27.30	2.46	2.46	966.60	14772.60	INR Fourteen Thousand Seven Hundred & Seventy Two and Paise Sixty Only
58	33kV Lightning Arrestor, 10KA, (Line type)	2	Set	25000.00	2250.00	2250.00	59000.00	1750.00	157.50	157.50	4130.00	63130.00	INR Sixty Three Thousand One Hundred & Thirty Only
59	Grouting & Muffling of Steel Tubular Poles	501	No.	2700.00	243.00	243.00	1596186.00	1200.00	108.00	108.00	709416.00	2305602.00	INR Twenty Three Lakh Five Thousand Six Hundred & Two Only
60	Grouting of Stay Set with PCC and Boulder	92	No.	200.00	18.00	18.00	21712.00	100.00	9.00	9.00	10856.00	32568.00	INR Thirty Two Thousand Five Hundred & Sixty Eight Only
61	Horizontal Boring of 350mm dia. for laying of UG Cable	330	Mtr.	500.00	45.00	45.00	194700.00	140.00	12.60	12.60	54516.00	249216.00	INR Two Lakh Forty Nine Thousand Two Hundred & Sixteen Only
62	Isolator Fencing as per REC standard specification complete with material & labour	2	Job	18000.00	1620.00	1620.00	42480.00	1200.00	108.00	108.00	2832.00	45312.00	INR Forty Five Thousand Three Hundred & Twelve Only
Total in Figures							103180877.96				10902599.44	114083477.40	INR Eleven Crore Forty Lakh Eighty Three Thousand Four Hundred & Seventy Seven and Paise Forty Only
Quoted Rate in Words													

12/05/2026
CGM (D&S)
APDCL (LAR)

Md

Preeti Barman
Dy General Manager
Olo the CGM (D&S), LAR, APDCL

Asstt. General Manager
Olo the CGM (D&S), APDCL, LAR

Tender Inviting Authority:

Name of Work: Construction of 33 KV UG Railway Track Crossing for 33 KV Dedicated feeder at Bhakarvita (near Ambedkar Hall to Track Depot NF Railway) in between KM 252/3 and 252/4 of Railway Track

Contract No:

M/s. U K ENTERPRISE																	
Bidding Firm / Company :																	
ANNEXURE 2																	
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	TEXT #
Sl. No.	Item Description	Quantity	Units	Unit Rate for Supply of material (in Rs.)	CGST on Supply of material @9% Rs. P	SGST on Supply of material @9% Rs. P	Total Amount for material inclusive of GST	Unit Rate for Erection of material (incl. testing and commissioning) (in Rs.)	CGST on Erection of material @9% Rs. P	SGST on Erection of material @9% Rs. P	Total Amount for material inclusive of GST	Total Amount (Supply + Erection) (Inclusive of All Applicable Taxes and Duties) (in Rs.)	TOTAL AMOUNT In Words				
1	2	4	5	13	14	15	16	17	18	19	53	54	55				
1	GI Steel Tubular Pole SP-76	8	No.	52000.00	4680.00	4680.00	490880.00	6240.00	561.60	561.60	58905.60	549785.60	INR Five Lakh Forty Nine Thousand Seven Hundred & Eighty Five and Paise Sixty Only				
2	GI Channel Cross-Arm (100x50x6x3200mm)	26	No.	3000.00	270.00	270.00	92040.00	210.00	18.90	18.90	6442.80	98482.80	INR Ninety Eight Thousand Four Hundred & Eighty Two and Paise Eighty Only				
3	GI Angle (50x50x6mm) for Cross-Bracing	86	Mtr.	370.00	33.30	33.30	37547.60	25.90	2.33	2.33	2628.16	40175.76	INR Forty Thousand One Hundred & Seventy Five and Paise Seventy Six Only				
4	GI Nuts & Bolts with Washers (assorted)	30	Kg.	100.00	9.00	9.00	3540.00	7.00	0.63	0.63	247.80	3787.80	INR Three Thousand Seven Hundred & Eighty Seven and Paise Eighty Only				
5	GI Jam Clamp with GI Angle 50x50x6mm	16	No.	250.00	22.50	22.50	4720.00	17.50	1.58	1.58	330.56	5050.56	INR Five Thousand & Fifty and Paise Fifty Six Only				
6	GI Pole Clamp with GI Flat 50x6mm	48	No.	210.00	18.90	18.90	11894.40	14.70	1.32	1.32	832.32	12726.72	INR Twelve Thousand Seven Hundred & Twenty Six and Paise Seventy Two Only				
7	33kV Grade XLPE Insulated Armoured 1-Core x 630 sqmm Cable	725	Mtr.	1800.00	162.00	162.00	153990.00	126.00	11.34	11.34	107793.00	1647693.00	INR Sixteen Lakh Forty Seven Thousand Six Hundred & Ninety Three Only				
8	Cable Termination Kit for 33kV Grade XLPE Insulated Armoured 1-Core x 630 sqmm Cable (Rate of 400sqmm)	10	No.	5000.00	450.00	450.00	59000.00	350.00	31.50	31.50	4130.00	63130.00	INR Sixty Three Thousand One Hundred & Thirty Only				
9	Polymeric Pin Insulator (FRP 34mm)	12	No.	790.00	71.10	71.10	11186.40	55.30	4.98	4.98	783.12	11969.52	INR Eleven Thousand Nine Hundred & Sixty Nine and Paise Fifty Two Only				
10	33kV Danger Plate	8	No.	180.00	16.20	16.20	1695.20	12.80	1.13	1.13	118.88	1818.08	INR One Thousand Eight Hundred & Eighteen and Paise Eight Only				
11	HT Stay Set	8	Set	700.00	63.00	63.00	6608.00	49.00	4.41	4.41	462.56	7070.56	INR Seven Thousand & Seventy and Paise Fifty Six Only				
12	33kV Grade Guy Insulator (Porcelain)	8	No.	50.00	4.50	4.50	472.00	3.50	0.32	0.32	33.12	505.12	INR Five Hundred & Five and Paise Twelve Only				
13	GI Stay Wire, 7/10 SWG	56	Kg.	64.00	5.76	5.76	4229.12	4.48	0.40	0.40	295.68	4524.80	INR Four Thousand Five Hundred & Twenty Four and Paise Eighty Only				
14	GI Wire 8 SWG for Earthing	25	Kg.	64.00	5.76	5.76	1888.00	4.48	0.40	0.40	132.00	2020.00	INR Two Thousand & Twenty Only				
15	GI Barbed Wire	16	Kg.	64.00	5.76	5.76	1208.32	4.48	0.40	0.40	84.48	1292.80	INR One Thousand Two Hundred & Ninety Two and Paise Eighty Only				
16	GI Earth Pipe 50mm. dia., 3mtr. length	8	No.	1800.00	162.00	162.00	16992.00	126.00	11.34	11.34	1189.44	18181.44	INR Eighteen Thousand One Hundred & Eighty One and Paise Forty Only				
17	HDPE Pipe PE100 110mm dia. Outer dia.	70	Mtr.	500.00	45.00	45.00	41300.00	35.00	3.15	3.15	2891.00	44191.00	INR Forty Four Thousand One Hundred & Ninety One Only				
18	CI Spun Pipe Class 1A type 300mm dia., 5.5Mtr. Length	23	No.	12000.00	1080.00	1080.00	325680.00	840.00	75.60	75.60	22797.60	348477.60	INR Three Lakh Forty Eight Thousand Four Hundred & Seventy Seven and Paise Sixty Only				
19	Bend for CI Spun Pipe	22	No.	1000.00	90.00	90.00	25960.00	70.00	6.30	6.30	1817.20	27777.20	INR Twenty Seven Thousand Seven Hundred & Seventy Seven and Paise Twenty Only				

20	33KV Lightning Arrestor, 10KA, Station-Type, with surge monitor & GI Mounting Structure	2	Set	2500.00	225.00	225.00	5900.00	175.00	15.75	413.00	6313.00	INR Six Thousand Three Hundred & Thirteen Only
21	33KV GOAB switch 800Amp	2	Set	30000.00	2700.00	2700.00	70800.00	2100.00	189.00	4956.00	75756.00	INR Seventy Five Thousand Seven Hundred & Fifty Six Only
22	Grouting & Muffling of Steel Tubular Poles	8	No.	2700.00	243.00	243.00	25488.00	1200.00	108.00	11328.00	36816.00	INR Thirty Six Thousand Eight Hundred & Sixteen Only
23	Grouting of 350mm dia. for laying of UG Cable	145	Mtr.	950.00	85.50	85.50	162645.00	250.00	22.50	42775.00	205320.00	INR Two Lakh Five Thousand Three Hundred & Twenty Only
24	Grouting of Stay Set with PCC and Boulder	8	No.	210.00	18.90	18.90	1982.40	100.00	9.00	944.00	2926.40	INR Two Thousand Nine Hundred & Twenty Six and Paise Forty Only
Total in Figures							2943460.44			272331.32	3215791.76	INR Thirty Two Lakh Fifteen Thousand Seven Hundred & Ninety One and Paise Seventy Six Only
Quoted Rate in Words												



 Rajya Deon
 Asstt. General Manager
 O/o the CGM (D&S) APDC, LAR



 P. V. Narasimha
 Asstt. General Manager
 O/o the CGM (D&S) APDC, LAR





Tender-Inviting Authority:
 Name of Work: Construction of 33 KV Spur line from 33/11 KV Birjhora Sub-Station to 33/11 KV Birjhora Medical College Feeder at Barpara near Arogya Hospital gate as alternate stand by source of power from 33/11 KV Birjhora Sub-Station and Construction of 11 KV & LT Composite lines for ROW of 33 KV Line
 Contract No:

Name of the Bidder/ Bidding Firm / Company :		ANNEXURE 3																				M/s. U K ENTERPRISE					
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	NUMBER	TEXT	TEXT	TEXT	TEXT	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units		Unit Rate for Supply of material (in Rs.)	CGST on Supply of material @9% Rs. P	SGST on Supply of material @9% Rs. P	Total Amount for Supply of material inclusive of GST	Unit Rate for Erection of material (incl. testing and commissioning) (in Rs.)	CGST on Erection of material @9% Rs. P	SGST on Erection of material @9% Rs. P	Total Amount for Erection of material inclusive of GST	Total Amount (Supply + Erection) (Inclusive of All Applicable Taxes and Duties) (in Rs.)		TOTAL AMOUNT In Words												
1	2	4	5		13	14	15	16	17	18	19	53	54	55													
1	GI Steel Tubular Pole SP-76	166	No.		52000.00	4680.00	4680.00	10185760.00	6240.00	561.60	561.60	1222291.20	11408051.20		INR One Crore Fourteen Lakh Eight Thousand & Fifty One and Paise Twenty Only												
2	GI Steel Tubular Pole SP-80	12	No.		54000.00	4860.00	4860.00	764640.00	6480.00	583.20	583.20	91756.80	856396.80		INR Eight Lakh Fifty Six Thousand Three Hundred & Ninety Six and Paise Eighty Only												
3	GI Channel Cross Arm (100x50x6x3200mm)	132	No.		3000.00	270.00	270.00	467280.00	210.00	18.90	18.90	32709.60	499989.60		INR Four Lakh Ninety Nine Thousand Nine Hundred & Eighty Nine and Paise Sixty Only												
4	GI Angle (50x50x6mm) for Cross-Bracing	720	Mtr.		370.00	33.30	33.30	314352.00	25.90	2.33	2.33	22003.20	336355.20		INR Three Lakh Thirty Six Thousand Three Hundred & Fifty Five and Paise Twenty Only												
5	GI 33KV V-Cross Arm with Channel size (100x50x6) mm	105	No.		2100.00	189.00	189.00	260190.00	147.00	13.23	13.23	18213.30	278403.30		INR Two Lakh Seventy Eight Thousand Four Hundred & Three and Paise Thirty Only												
6	GI Top Cleat of Channel 100x50x6x350mm	105	No.		360.00	32.40	32.40	44604.00	25.20	2.27	2.27	3122.70	47726.70		INR Forty Seven Thousand Seven Hundred & Twenty Six and Paise Seventy Only												
7	GI Angle (50x50x6mm) for Guarding	458	Mtr.		370.00	33.30	33.30	199862.80	25.90	2.33	2.33	13996.48	213959.28		INR Two Lakh Thirteen Thousand Nine Hundred & Fifty Nine and Paise Twenty Eight Only												
8	GI Nuts & Bolts with Washers (assorted)	550	Kg.		210.00	18.90	18.90	136290.00	14.70	1.32	1.32	9537.00	145827.00		INR One Lakh Forty Five Thousand Eight Hundred & Twenty Seven Only												
9	GI Tie Angle (50x50x6x1000mm)	210	No.		370.00	33.30	33.30	91686.00	25.90	2.33	2.33	6417.60	98103.60		INR Ninety Eight Thousand One Hundred & Three and Paise Sixty Only												
10	GI Pole Clamp with GI Flat 50x6mm	515	No.		210.00	18.90	18.90	127617.00	14.70	1.32	1.32	8930.10	136547.10		INR One Lakh Thirty Six Thousand Five Hundred & Forty Seven and Paise Ten Only												
11	33KV 1-Core x 241sqmm AAAC Triple Extruded Covered Conductor	14070	Mtr.		790.00	71.10	71.10	13116054.00	84.00	7.56	7.56	1394618.40	14510672.40		INR One Crore Forty Five Lakh Ten Thousand Six Hundred & Seventy Two and Paise Forty Only												
12	33KV Mid-span Joining Kit for 33KV 1-Core x 241sqmm AAAC Covered Conductor	30	No.		2100.00	189.00	189.00	74340.00	147.00	13.23	13.23	5203.80	79543.80		INR Seventy Nine Thousand Five Hundred & Forty Three and Paise Eighty Only												
13	33KV Cable Termination Kit for 1-Core x 241sqmm AAAC Covered Conductor	162	No.		2100.00	189.00	189.00	401436.00	147.00	13.23	13.23	28100.52	429536.52		INR Four Lakh Twenty Nine Thousand Five Hundred & Thirty Six and Paise Fifty Two Only												
14	Polymeric Pin Insulator (FRP 34mm)	450	No.		790.00	71.10	71.10	419490.00	55.30	4.98	4.98	29367.00	448857.00		INR Four Lakh Forty Eight Thousand Eight Hundred & Fifty Seven Only												
15	33KV Tension Insulator for 1-Core x 241sqmm AAAC Covered Conductor	192	No.		790.00	71.10	71.10	178982.40	55.30	4.98	4.98	12529.92	191512.32		INR One Lakh Ninety One Thousand Five Hundred & Twelve and Paise Thirty Two Only												
16	33KV Tension Hardware for 1-Core x 241sqmm AAAC Covered Conductor	192	No.		1600.00	144.00	144.00	362496.00	112.00	10.08	10.08	25374.72	387870.72		INR Three Lakh Eighty Seven Thousand Eight Hundred & Seventy and Paise Seventy Two Only												

17	33kV Cable Tie for 1-Core x 241sqmm AAC Covered Conductor	450	No.	1000.00	90.00	90.00	531000.00	70.00	6.30	6.30	37170.00	568170.00	INR Five Lakh Sixty Eight Thousand One Hundred & Seventy Only
18	33kV Danger Plate	178	No.	180.00	16.20	16.20	37807.20	12.60	1.13	1.13	2646.08	40452.28	INR Forty Thousand Four Hundred & Fifty Two and Paise Twenty Eight Only
19	HT Stay Set	70	Set	700.00	63.00	63.00	57820.00	49.00	4.41	4.41	4047.40	61867.40	INR Sixty One Thousand Eight Hundred & Sixty Seven and Paise Forty Only
20	33kV Grade Guy Insulator (Porcelain)	70	No.	50.00	4.50	4.50	4130.00	3.50	0.32	0.32	289.80	4419.80	INR Four Thousand Four Hundred & Nineteen and Paise Eighty Only
21	GI Stay Wire, 7/10 SWG	700	Kg.	64.00	5.76	5.76	52864.00	4.48	0.40	0.40	3696.00	56560.00	INR Fifty Six Thousand Five Hundred & Sixty Only
22	GI Wire 8 SWG for Guarding & Earthing	3000	Kg.	64.00	5.76	5.76	226560.00	4.48	0.40	0.40	15840.00	242400.00	INR Two Lakh Forty Two Thousand Four Hundred Only
23	GI Barbed Wire	178	Kg.	64.00	5.76	5.76	13442.56	4.48	0.40	0.40	939.84	14382.40	INR Fourteen Thousand Three Hundred & Eighty Two and Paise Forty Only
24	GI Earth Pipe 50mm. dia., 3mtr. length	178	No.	1800.00	162.00	162.00	378072.00	126.00	11.34	11.34	26465.04	404537.04	INR Four Lakh Four Thousand Five Hundred & Thirty Seven and Paise Four Only
25	33kV Grade Isolator, TPQO-DCBR without earth switch and GI Mounting Structure, 800 Amps	1	Set	70000.00	6300.00	6300.00	82600.00	4900.00	441.00	441.00	5782.00	89382.00	INR Eighty Eight Thousand Three Hundred & Eighty Two Only
26	11kV Pin Insulator Polymeric	417	No.	500.00	45.00	45.00	246030.00	35.00	3.15	3.15	17222.10	263252.10	INR Two Lakh Sixty Three Thousand Two Hundred & Fifty Two and Paise Ten Only
27	ACSR Raccoon Conductor	12.5	KM	84000.00	7560.00	7560.00	1239000.00	5880.00	529.20	529.20	86730.00	1325730.00	INR Thirteen Lakh Twenty Five Thousand Seven Hundred & Thirty Only
28	1kV Grade Disc Insulator (Polymer) 70kN (T&C Type)	168	No.	500.00	45.00	45.00	99120.00	35.00	3.15	3.15	6938.40	106058.40	INR One Lakh Six Thousand & Fifty Eight and Paise Forty Only
29	H/W Fittings for Raccoon	168	No.	500.00	45.00	45.00	99120.00	35.00	3.15	3.15	6938.40	106058.40	INR One Lakh Six Thousand & Fifty Eight and Paise Forty Only
30	Tension Clamp for Raccoon	168	No.	180.00	16.20	16.20	36683.20	12.60	1.13	1.13	2496.48	38179.68	INR Thirty Eight Thousand One Hundred & Seventy Nine and Paise Sixty Eight Only
31	PG Clamp for Raccoon	168	No.	300.00	27.00	27.00	59472.00	21.00	1.89	1.89	4183.04	63635.04	INR Sixty Three Thousand Six Hundred & Thirty Five and Paise Four Only
32	GI Channel Cross Arm (100X50X6X220mm) side bracing for 11kV Composite Line	110	No.	1800.00	162.00	162.00	233640.00	126.00	11.34	11.34	16354.80	249994.80	INR Two Lakh Forty Nine Thousand Nine Hundred & Ninety Four and Paise Eighty Only
33	GI LT Angle Cross Arm (40x40x6x500)mm	65	No.	250.00	22.50	22.50	19175.00	17.50	1.58	1.58	1342.90	20517.90	INR Twenty Thousand Five Hundred & Seventeen and Paise Ninety Only
34	LT Pin Insulator (Porcelain)	50	No.	50.00	4.50	4.50	2950.00	3.50	0.32	0.32	207.00	3157.00	INR Three Thousand One Hundred & Fifty Seven Only
35	LT GI Pin	50	No.	25.00	2.25	2.25	1475.00	1.75	0.16	0.16	103.50	1578.50	INR One Thousand Five Hundred & Seventy Eight and Paise Fifty Only
36	Shackle Insulator Porcelain	40	No.	50.00	4.50	4.50	2360.00	3.50	0.32	0.32	165.60	2525.60	INR Two Thousand Five Hundred & Twenty Five and Paise Sixty Only
37	LT GI Shackle Strap with Bolts	40	No.	25.00	2.25	2.25	1180.00	1.75	0.16	0.16	82.80	1252.80	INR One Thousand Two Hundred & Sixty Two and Paise Eighty Only
38	Pole Clamp of GI Flat 50x6mm	65	No.	100.00	9.00	9.00	7670.00	7.00	0.63	0.63	536.90	8206.90	INR Eight Thousand Two Hundred & Six and Paise Ninety Only
39	ACSR "RABBIT" Conductor	2.2	KM	64000.00	5760.00	5760.00	166144.00	4480.00	403.20	403.20	11630.08	177774.08	INR One Lakh Seventy Seven Thousand Seven Hundred & Seventy Four and Paise Eight Only
40	33kV Combined CT-PT Set, 150/5A, Accuracy Class 0.2	1	Set	0.00	0.00	0.00	0.00	7000.00	630.00	630.00	8260.00	8260.00	INR Eight Thousand Two Hundred & Sixty Only
41	Metering Cabinet	1	No.	6300.00	567.00	567.00	7434.00	441.00	39.69	39.69	520.38	7964.38	INR Seven Thousand Nine Hundred & Fifty Four and Paise Thirty Eight Only
42	Copper Control Cable, 10-Core x 2.5sq.mm.	15	Mtr.	390.00	35.10	35.10	6903.00	27.30	2.46	2.46	483.30	7386.30	INR Seven Thousand Three Hundred & Eighty Six and Paise Thirty Only
43	33kV Lightning Arrestor, 10KA, Station-Type, with surge monitor & GI Mounting Structure	1	Set	25000.00	2250.00	2250.00	29500.00	1750.00	157.50	157.50	2065.00	31565.00	INR Thirty One Thousand Five Hundred & Sixty Five Only
44	Grouting & Muffling of Steel Tubular Poles	178	No.	1000.00	90.00	90.00	210040.00	1200.00	108.00	108.00	25204.80	462088.00	INR Four Lakh Sixty Two Thousand & Eighty Eight Only
45	Grouting of Stay Set with PCC and Boulder	70	No.	500.00	45.00	45.00	41300.00	2500.00	225.00	225.00	206500.00	247800.00	INR Two Lakh Forty Seven Thousand Eight Hundred Only
46	RCC Foundation for 33kV Isolator	1	No.	18000.00	1620.00	1620.00	21240.00	7000.00	630.00	630.00	8260.00	29500.00	INR Twenty Nine Thousand Five Hundred Only
47	Isolator Fencing as per REC standard specification complete with material & labour	1	Job	25000.00	2250.00	2250.00	29500.00	4500.00	405.00	405.00	5310.00	34810.00	INR Thirty Four Thousand Eight Hundred & Ten Only

Total in Figures	31088412.16 3659406.18 34747818.34 INR Three Crore Forty Seven Lakh Forty Seven Thousand Eight Hundred & Eighteen and Paise Thirty Four Only
Quoted Rate in Words	

[Signature]

[Signature]

[Signature]
 Papya Deori
 Asstt. General Manager
 O/o the CGM (D&S) APDCL, LAR

Tender-Inviting Authority:

Name of Work: Construction of Terminal Bay at the 33/11 KV Birjhora Sub-Station for 33 KV Feeder from 33 KV Birjhora Sub-Station to 33/11 KV Bonggaon Medical College Feeder (near Arogya Hospital Gate)

Contract No:

ANNEXURE 4													
Name of the Bidder/ Bidding Firm / Company : M/s. J K ENTERPRISE													
Sl. No.	Item Description	NUMBER #	TEXT #	NUMBER #	UNIT Rate for Supply of material (in Rs.)	NUMBER	CGST on Supply of material @9% Rs. P	NUMBER	SGST on Supply of material @9% Rs. P	NUMBER	Total Amount for Supply of material inclusive of GST	NUMBER	Unit Rate for Erection of material (incl. testing and commissioning) (in Rs.)
		Quantity	Units	TEXT #	NUMBER #	NUMBER	CGST on Supply of material @9% Rs. P	NUMBER	SGST on Supply of material @9% Rs. P	NUMBER	Total Amount for Supply of material inclusive of GST	NUMBER	Unit Rate for Erection of material (incl. testing and commissioning) (in Rs.)
1	2	4	5		13	15	14	16	17	18	19	55	
1	GI Steel Tubular Pole SP-66	4	No.		34000.00	3060.00	3080.00	160480.00	4080.00	367.20	19257.60	54	179737.60
2	33KV Grade Isolator, TPGO-DBCR without Earth switch but with GI Mounting Structure 800 Amps	3	Set		55000.00	4950.00	4950.00	194700.00	3850.00	346.50	13629.00	208329.00	INR One Lakh Seventy Nine Thousand Seven Hundred & Thirty Seven and Paise Sixty Only
3	33KV 10KA Lighting Arrester with Surge Monitor & GI Mounting Structure (Station Type)	1	Set		25000.00	2250.00	2250.00	29500.00	1750.00	157.50	2056.00	31565.00	INR Two Lakh Eight Thousand Three Hundred & Twenty Nine Only
4	33KV VCB 1250A with GI Mounting Structure	1	Set		250000.00	22500.00	22500.00	295000.00	17500.00	1575.00	20650.00	315650.00	INR Thirty One Thousand Five Hundred & Sixty Five Only
5	33KV C&R Panel for Feeder Protection	1	No.		270000.00	24300.00	24300.00	318600.00	18900.00	1701.00	22302.00	340902.00	INR Three Lakh Fifty Thousand Nine Hundred & Two Only
6	33KV CT 0.5 Class 1ph Outdoor CT with GI mounting structure & marshaling Box (Set comprising of three units) 400-200/5-5-5A, 25kA for 3 sec	1	Set		140000.00	12600.00	12600.00	166200.00	9800.00	882.00	11564.00	176764.00	INR One Lakh Seventy Six Thousand Seven Hundred & Sixty Four Only
7	GI Channel for 33 KV Bus 100x50x6 mm	48	Mtr.		700.00	63.00	63.00	39648.00	49.00	4.41	2775.36	42423.36	INR Forty Two Thousand Four Hundred & Twenty Three and Paise Thirty Six Only
8	Copper Control Cable 10 Core 2.5 Sqmm	50	Mtr.		390.00	35.10	35.10	23010.00	27.30	2.46	1611.00	24621.00	INR Twenty Four Thousand Six Hundred & Twenty One Only
9	Copper Control Cable 4 Core 2.5 Sqmm	230	Mtr.		250.00	22.50	22.50	67850.00	17.50	1.58	4751.80	72601.80	INR Seventy Two Thousand Six Hundred & One and Paise Eighty Only
10	Polymeric Pin Insulator (FRP 34mm)	12	No.		410.00	36.90	36.90	5805.60	28.70	2.58	406.32	6211.92	INR Six Thousand Two Hundred & Eleven and Paise Ninety Two Only
11	33KV Polymeric Disc Insulator, 90 KN, T&C	18	No.		410.00	36.90	36.90	8708.40	28.70	2.58	609.48	9317.88	INR Nine Thousand Three Hundred & Seventeen and Paise Eighty Eight Only
12	H/W Fittings for 33kv Disc Insulator, T&C, Tension Type	18	No.		450.00	40.50	40.50	9558.00	31.50	2.84	689.24	10227.24	INR Ten Thousand Two Hundred & Twenty Seven and Paise Twenty Four Only
13	Tension Clamp for Wolf conductor	18	No.		250.00	22.50	22.50	5310.00	17.50	1.58	371.88	5681.88	INR Five Thousand Six Hundred & Eighty One and Paise Eighty Eight Only
14	GI Nuts & Bolts with Washers (assorted)	40	Kg.		100.00	9.00	9.00	4720.00	7.00	0.63	330.40	5050.40	INR Five Thousand & Fifty and Paise Forty Only
15	ACSR Wolf Conductor	0.3	KM		180000.00	16200.00	16200.00	63720.00	12600.00	1134.00	4460.40	68180.40	INR Sixty Eight Thousand One Hundred & Eighty and Paise Forty Only
16	PG Clamp for Wolf Conductor	30	No.		250.00	22.50	22.50	8850.00	17.50	1.58	619.80	9469.80	INR Nine Thousand Four Hundred & Sixty Nine and Paise Eighty Only
17	GI Pole Clamp with GI Flat 50x6mm	25	No.		100.00	9.00	9.00	2950.00	7.00	0.63	206.50	3166.50	INR Three Thousand One Hundred & Fifty Six and Paise Fifty Only
18	33KV DO Fuse 150A Assembly	1	Set		18000.00	1620.00	1620.00	21240.00	1260.00	113.40	1486.80	22728.80	INR Twenty Two Thousand Seven Hundred & Twenty Six and Paise Eighty Only
19	33KV GOAB switch 400Amp	1	Set		30000.00	2700.00	2700.00	35400.00	2100.00	189.00	2478.00	37878.00	INR Thirty Seven Thousand Eight Hundred & Seventy Eight Only

20	GI Earth Pipe 50mm. dia., 3mtr. length	6	No.	1000.00	90.00	90.00	7080.00	70.00	6.30	6.30	495.60	7575.60	INR Seven Thousand Five Hundred & Seventy Five and Paise Sixty Only
21	GI Strip 25x3mm for DTR earthing	10	Mtr.	100.00	9.00	9.00	1180.00	7.00	0.63	0.63	82.60	1262.60	INR One Thousand Two Hundred & Sixty Two and Paise Sixty Only
22	GI strip 50x6mm for DTR Neutral earthing	10	Mtr.	250.00	22.50	22.50	2950.00	17.50	1.58	1.58	206.60	3166.60	INR Three Thousand One Hundred & Fifty Six and Paise Sixty Only
23	GI Channel Cross-Arm (100x50x6x3200mm)	9	No.	3000.00	270.00	270.00	31860.00	210.00	18.90	18.90	2230.20	34090.20	INR Thirty Four Thousand & Ninety and Paise Twenty Only
24	Installation of earthing system with MS flats 50x10mm (for earthing mat) with GI flat riser 25x6mm (for earthing conductor) and GI pipe 50mm dia of length 3000mm for earth electrodes including excavation of earth welding etc. as necessary	70	Sqm	450.00	40.50	40.50	37170.00	31.50	2.84	2.84	2602.60	39772.60	INR Thirty Nine Thousand Seven Hundred & Seventy Two and Paise Sixty Only
25	Switch yard graveling of 0.15 mtr. (thickness) by 40mm size crushed stone	70	Sqm	390.00	35.10	35.10	32214.00	27.30	2.46	2.46	2255.40	34469.40	INR Thirty Four Thousand Four Hundred & Sixty Nine and Paise Forty Only
26	33KV Combined CT-PT Set, 150/5 A, Accuracy Class 0.2	1	Set	0.00	0.00	0.00	0.00	7000.00	630.00	630.00	8260.00	8260.00	INR Eight Thousand Two Hundred & Sixty Only
27	Metering Cabinet	1	No.	6300.00	567.00	567.00	7434.00	441.00	39.69	39.69	520.38	7964.38	INR Seven Thousand Nine Hundred & Fifty Four and Paise Thirty Eight Only
28	Copper Control Cable, 10-Core, 2.5 sq.mm.	15	Mtr.	390.00	35.10	35.10	6903.00	27.30	2.46	2.46	483.30	7386.30	INR Seven Thousand Three Hundred & Eighty Six and Paise Thirty Only
29	33KV Lightning Arrestor, 10KA, (Line type)	1	Set	25000.00	2250.00	2250.00	29500.00	1750.00	157.50	157.50	2065.00	31565.00	INR Thirty One Thousand Five Hundred & Sixty Five Only
30	Grouting & Muffling of Steel Tubular Poles	4	No.	1000.00	90.00	90.00	4720.00	1200.00	108.00	108.00	5664.00	10384.00	INR Ten Thousand Three Hundred & Eighty Four Only
31	RCC Foundation for 33KV Isolator	3	No.	18000.00	1620.00	1620.00	63720.00	1260.00	113.40	113.40	4460.40	68180.40	INR Sixty Eight Thousand One Hundred & Eighty and Paise Forty Only
32	RCC foundation for 33KV CT	3	No.	18000.00	1620.00	1620.00	63720.00	1260.00	113.40	113.40	4460.40	68180.40	INR Sixty Eight Thousand One Hundred & Eighty and Paise Forty Only
33	RCC foundation for VCB	1	No.	18000.00	1620.00	1620.00	21240.00	1260.00	113.40	113.40	1486.80	22726.80	INR Twenty Two Thousand Seven Hundred & Twenty Six and Paise Eighty Only
34	RCC foundation for 33KV LA as per standard drawing and technical specifications(per No.)	3	No.	5000.00	450.00	450.00	17700.00	350.00	31.50	31.50	1239.00	18939.00	INR Eighteen Thousand Nine Hundred & Thirty Nine Only
Total in Figures							1787641.00				146756.86	1934397.86	INR Nineteen Lakh Thirty Four Thousand Three Hundred & Ninety Seven and Paise Eighty Six Only
Quoted Rate in Words													


 Pooja Deori
 Asstt. General Manager
 C/o the CGM (D&S) APDCL, LAR

Item Wise BoQ

Tender Inviting Authority:
 Name of Work: Dismantling of 11 KV & LT lines of 11 KV Bageswari feeder, 11 KV Bongalgaon Civil Hospital Feeder and 11 KV Dhaligaon feeder under BESD-II for ROW of 33 KV Dedicated Feeder from Dhaligaon GSS to Bongalgaon Medical College at Majgaon, Bongalgaon and 33/11 KV Birjhora DSS to Bongalgaon Medical Hospital feeder at Barpara, or providing 33 KV power supply to the premises of "New Medical College & Hospital, Majgaon"
 Contract No.:

ANNEXURE 5													
Name of the Bidder/ Bidding Firm / Company :													
Sl. No.	Item Description	Quantity	TEXT #	NUMBER #	TEXT #	Unit Rate for Supply of material (in Rs.)	NUMBER #	CGST on Supply of material @9% Rs. P	NUMBER #	SGST on Supply of material @9% Rs. P	NUMBER #	Total Amount for Supply of material inclusive of GST	NUMBER #
1	2	4	5	13	14	15	16	17	18	19	20	21	22
1	Dismantling of 9.75 m FSC Pole	92	No.	0.00			0.00	700.00	63.00	63.00	75992.00	54	55
2	Dismantling of Rail/Steel tubular pole from the existing lines and S/S including loading and unloading and transportation from work site to depts. store	101	No.	0.00			0.00	700.00	63.00	63.00	83426.00	83426.00	INR Eighty Three Thousand Four Hundred & Twenty Six Only
3	Dismantling of Ch. Cross Arm: 100 X 50 X 6 X 2200 mm	46	No.	0.00			0.00	300.00	27.00	27.00	16284.00	16284.00	INR Sixteen Thousand Two Hundred & Eighty Four Only
4	Dismantling of T cross arm	131	No.	0.00			0.00	100.00	9.00	9.00	15458.00	15458.00	INR Fifteen Thousand Four Hundred & Fifty Eight Only
5	Dismantling of 11KV pin insulator	402	No.	0.00			0.00	30.00	2.70	2.70	14230.80	14230.80	INR Fourteen Thousand Two Hundred & Thirty and Paise Eighty Only
6	Dismantling of Disc Insulator with hardware(single disc)	103	No.	0.00			0.00	50.00	4.50	4.50	6077.00	6077.00	INR Six Thousand & Seventy Seven Only
7	Dismantling of Racoon conductor	21	per KM	0.00			0.00	3000.00	270.00	270.00	74340.00	74340.00	INR Seventy Four Thousand Three Hundred & Forty Only
8	Dismantling of HT stay set including stay wire and insulator	8	No.	0.00			0.00	100.00	9.00	9.00	944.00	944.00	INR Nine Hundred & Forty Four Only
9	Dismantling of LT Cross Arm	182	No.	0.00			0.00	50.00	4.50	4.50	10738.00	10738.00	INR Ten Thousand Seven Hundred & Thirty Eight Only
10	Dismantling of LT Pin Insulator with GI Pin	346	No.	0.00			0.00	10.00	0.90	0.90	4082.80	4082.80	INR Four Thousand & Eighty Two and Paise Eighty Only
11	Dismantling of LT Shackle Insulator	96	No.	0.00			0.00	10.00	0.90	0.90	1132.80	1132.80	INR One Thousand One Hundred & Thirty Two and Paise Eighty Only
12	Dismantling of Weasel conductor	20	per KM	0.00			0.00	1800.00	162.00	162.00	42480.00	42480.00	INR Forty Two Thousand Four Hundred & Eighty Only
Total in Figures							0.00				345185.40	345185.40	INR Three Lakh Forty Five Thousand One Hundred & Eighty Five and Paise Forty Only
Quoted Rate in Words													

Asstt. General Manager
 Papiya Deori
 Asstt. General Manager
 Papiya Deori
 Asstt. General Manager
 Papiya Deori

Asstt. General Manager
 Papiya Deori
 Asstt. General Manager
 Papiya Deori
 Asstt. General Manager
 Papiya Deori

Asstt. General Manager
 Papiya Deori

Asstt. General Manager
 Papiya Deori